

## Stratford Supply Channel Pipeline

### Date

May 2013 – August 2013

### Location

Stratford, Victoria

### Client

Southern Rural Water

### Project value

\$300K

### Project Details

JAYDO was engaged as contractor to deliver 1.1km of DN375 PVC pipeline replacement for channel sections by Southern Rural Water. These works were carried out within private properties and required stock and domestic pipeline installation.

The Project Scope included:

- Removal of concrete channel and structures and deposited at authorized EPA location
- Construction of 1020m of 375mm PVC Pipeline includes air and scour valves plus inspection points
- SRW inlet and outlet structure

- Private inlet and outlet structure
- Commissioning and pressure testing of pipeline including reporting
- Construction of HDPE pipe 315mm diameter 360m long include inlet and outlet structures
- Construct a 250m long farm channel and fill in of earthen channel (700 metres)

### Key Challenges

Minimizing the impact on farmers land and gaining acceptance from farmers of reinstatement works. In addition to meeting timeframes with unfavourable weather conditions.

### Client Feedback

JAYDO completed this project, commissioned ready for water to be delivered to customers within the client timeframes provided.



### JAYDO CONSTRUCTION

54 Henderson Road, Rowville, VIC 3178, Australia  
T: (03) 9763 3644 F: (03) 9763 3655 E: enquiries@jaydo.com.au

ABN 16 062 221 596

[jaydo.com.au](http://jaydo.com.au)